

The purpose of this document is to provide water customers with guidance on what will be assessed by Altogether before connecting their home to the wastewater system and making it habitable to move in.

- ALL of the criteria will need to be met prior to connecting your home

TERM	DEFINITION
General	<ul style="list-style-type: none"> • The build (as it relates to water and wastewater services) has been completed strictly as per the Altogether-approved plans • No-one has moved in before Altogether has made the wastewater connection operational
Recycled water uses	<ul style="list-style-type: none"> • There is only one cold water tap that supplies each washing machine and it is connected to recycled water • There is a minimum of two outdoor recycled water taps and they are labelled as 'Do Not Drink' • All toilets are connected to recycled water • Any bidets installed have the appropriate backflow prevention in place
On-lot Altogether infrastructure:	<ul style="list-style-type: none"> • The wastewater collection tank, boundary kit and pump control panel are readily accessible and not buried or damaged • The wastewater collection tank is a minimum of 2 metres from the house (unless otherwise mitigated and approved by Altogether Group) • The wastewater collection tank is a minimum of 0.5 metres from driveways, retaining walls, fences, bushes, and trees • The landscaping around the wastewater collection tank is compliant with Altogether's Landscaping Guide • Inside the wastewater collection tank is free and clear of all liquid and debris (this can be done the day before your connection booking)
Plumbing	<ul style="list-style-type: none"> • Evidence of plumbing check by plumbing regulator • Plumbing passes a cross-connection check • Overflow relief gully set in compliance with Plumbing Code and 75mm above proposed finished surface level
Pool plumbing (if applicable)	<ul style="list-style-type: none"> • The pool plumbing is compliant with Altogether's Pool and Spa Drainage Connection Requirements
Electrical	<ul style="list-style-type: none"> • Altogether electrical installation diagram has been followed correctly (Refer to drawing FSI-1003-FS) • Drawstrings have been pulled through all conduits • The conduit distance from the pump control panel to the wastewater collection tank is less than 35m • The pump control panel power supply has its own electrical circuit and is labelled correctly
Street reticulation	<ul style="list-style-type: none"> • The driveway has not been constructed in the immediate vicinity of street reticulation hydrants, valves, and flushing points
Payment	<ul style="list-style-type: none"> • All relevant fees and charges have been paid in full